

A hot air driven thermoacoustic-Stirling engine

M.E.H. Tijani*, S. Spoelstra

Energy Research Centre of the Netherlands (ECN), PO Box 1, 1755 ZG Petten, The Netherlands



ARTICLE INFO

Article history:

Received 29 January 2013

Accepted 9 April 2013

Available online 9 May 2013

Keywords:

Thermoacoustics

Engine

Stirling

ABSTRACT

Significant energy savings can be obtained by implementing a thermally driven heat pump into industrial or domestic applications [1]. Such a thermally driven heat pump uses heat from a high-temperature source to drive the system which upgrades an abundantly available heat source (industrial waste heat, air, water, geothermal). A way to do this is by coupling a thermoacoustic engine with a thermoacoustic heat pump. The engine is driven by a burner and produces acoustic power and heat at the required temperature. The acoustic power is used to pump heat in the heat pump to the required temperature. This system is attractive since it uses a noble gas as working medium and has no moving mechanical parts or sliding seals. This paper deals with the first part of this system: the engine. In this study, hot air is used to simulate the flue gases originating from a gas burner. This is in contrast with a lot of other studies of thermoacoustic engines that use an electrical heater as heat source. Using hot air resembles to a larger extent the real world application. The engine produces about 300 W of acoustic power with a performance of 41% of the Carnot performance at a hot air temperature of 620 °C.

© 2013 Elsevier Ltd. All rights reserved.

1. Introduction

Conventional engines generate work from heat by moving a piston or turning a turbine. Thermoacoustic engines in contrast have no mechanical moving parts or sliding seals involved in the power cycle which makes them very reliable. They have also the advantages of using only an environmentally friendly working medium (noble gases), simple implementation, and the use of common materials. The thermodynamic cycle used by a thermoacoustic traveling-wave engine is similar to the Stirling cycle. In 1979, it was recognized that the time phasing between the pressure and velocity of the gas in the regenerator of a Stirling system is the same as in a traveling acoustic wave [2]. In an attempt to eliminate the moving mechanical parts in a conventional Stirling engine, Ceperley [2] built a traveling-wave thermoacoustic engine which consists simply of a regenerator sandwiched between two heat exchangers placed inside an air filled looped tube. However, the engine didn't function due to large viscous losses in the regenerator and to mass streaming in the tube. It is only in 1999 that the first efficient thermoacoustic-Stirling engine was built by Backhaus et al. [3]. This engine converts heat into acoustic power with a thermal efficiency of 30%, corresponding to 41% of the Carnot efficiency without moving mechanical parts. In 2009, Tijani et al. developed a

thermoacoustic-Stirling engine which achieved a record performance of 49% of the Carnot performance [4]. These achievements will pave the way for the thermoacoustic technology to industrial applications.

This paper presents the design, construction, and test of a hot air driven thermoacoustic heat engine. The engine uses heat Q_h from hot air at a high temperature T_h to generate acoustic power W_a . Part of the acoustic power is dissipated in the acoustic resonator (tube) and the rest (useful) is dissipated in a dummy variable acoustic load. The remaining heat (Q_a) and the dissipated acoustic power (Q_r and Q_l) are rejected to the environment (T_a) as shown in Fig. 1. The foreseeable industrial application requires that the engine achieves a performance of 40% of the Carnot performance. The work presented in this paper concerns the design, development, and test of the engine.

The remaining of this paper is organized as follow: Section 2 describes the working principle, design, and construction of the engine. Section 3 is devoted to the measurements procedure. Section 4 presents the experimental results. In Section 5 some conclusions are drawn.

2. Design and construction of the thermoacoustic engine

A schematic illustration of the thermoacoustic Stirling-engine is shown in Fig. 2. The thermoacoustic engine consists of a torus-shaped section attached to a quarter-wavelength acoustic resonator and to a variable acoustic load. The system is filled with a

* Corresponding author. Tel.: +31 (0) 2224 564029.

E-mail address: tijani@ecn.nl (M.E.H. Tijani).




Fig. 1. Thermodynamic illustration of the thermoacoustic heat engine.

working gas (helium) at a given pressure. The torus-shaped section contains the thermodynamic active part consisting of a regenerator (REG.) sandwiched between two heat exchangers AHX1 and HHX. The regenerator is the heart of the engine where the thermoacoustic conversion processes take place. The thermoacoustic-Stirling heat engine functions like an acoustic amplifier. The application of heat to the HHX while maintaining AHX1 at ambient temperature creates a temperature difference across the regenerator which generates spontaneously an acoustic wave [2,3]. The acoustic wave takes care of the compression, displacement, expansion, and the timing necessary for the Stirling cycle. To keep the process ongoing, part of the acoustic power is fed back through the feedback tube (L) to the ambient side (AHX1) of the regenerator to be amplified.

The remainder of the acoustic power is available as useful power at the junction to the resonator. The gas column in the thermal buffer tube (TBT) provides thermal insulation for HHX. A secondary ambient heat exchanger (AHX2) is placed at the end of the TBT to intercept the heat leaking down the TBT. A drawing of the torus part of the engine part is shown in Fig. 3.

The acoustic resonator is of a quarter wavelength type consisting of a straight cylindrical tube with a small diameter connected to a larger diameter cylindrical tube by means of a conical tube. The variable acoustic load, consisting of a tank and an adjustable valve, controls the power output of the engine.

The thermoacoustic computer code DeltaEC [5] is used to design and optimize the engine. The engine uses helium at 40 bar and the operation frequency is 120 Hz. Air, driven by a blower and heated by an electrical heater is used as heat source and water flow chilled by a thermostat bath carries away the heat rejected by the engine at AHX1. The different components of the engine as incorporated in the DeltaEC-model are indicated in Fig. 2. A summary of the optimized dimensions of the different parts of the engine is given in the following.

The regenerator consists of a 6 cm long stack of 180-mesh stainless steel screens with a diameter of 6.7 cm. The diameter of the screen wire is 40 μm . A volume porosity of 78% and a hydraulic

radius of 35 μm are calculated using the mesh-number and wire diameter.

To avoid structural and gas leakage problems which might appear due to the high temperature and high pressure; the regenerator holder, HHX, and TBT are made from a single high temperature steel block as shown in Fig. 4 (middle).

The first ambient heat exchanger (AHX1) is of cross-flow type and consists of a cylindrical brass block with a length in the acoustical direction of 2 cm and a diameter of 6.7 cm containing copper fins at the helium-side to increase the heat transfer area. The water-side consists of rectangular channels (slits) 1 mm high and 15 mm wide. A picture of AHX1 is shown in Fig. 4 (left).

The hot heat exchanger (HHX) is the most crucial component of the engine as it has to transfer heat between hot air and the working gas (helium). It is chosen to use a finfin cross-flow heat exchanger. The optimization of the heat exchanger consists of transferring the needed heat with minimal pressure drop. Slits are made in the block for both helium- and air-side using an EDM technique. However, because of the length of the slits and the difficulty to access them, this process took a long time and the cost was proportionally high. Stainless steel fins are brazed in the slits to improve heat transfer between helium and air. For the helium side 50 fins/inch are used with a length in the acoustical direction of 5 cm and a height of 1 mm. For the air side 20 fins/inch are used with a cross-flow length of 7.5 cm, a width in the acoustical direction of 4.5 cm, and a height of 2 mm.

The hot heat exchanger is designed to exchange 2 kW of heat between the hot air and helium gas. The length in the acoustic direction is determined by the peak–peak displacement of helium, which is 5 cm; and the diameter of the heat exchanger has the same diameter as the regenerator, which is 6.7 cm. The second ambient heat exchanger (AHX2) consists of a circular brass block containing 782 holes with a diameter of 1.5 mm and a length of 1 cm through which the helium gas oscillates. Water flows around the perimeter of this block to carry away the heat leaking down the TBT. A picture of AHX2 is shown in Fig. 4 (right). The thermal buffer tube consists of a thin-walled cylindrical tube with an inside diameter of 7 cm, a wall thickness of 1.6 mm, and a length of 17 cm. It is made in the same block as the HHX as shown in Fig. 4. The feedback inductance consists of cylindrical tube with a length of 73 cm and diameter of 6.7 cm. The pressure balanced sliding joint is used to compensate the thermal expansion of the hot parts of the engine. This will avoid the building of stress in the hot walls and hence the damage of these parts. The variable acoustic load consists of a 1 L tank and an adjustable valve. As indicated earlier, the resonator consists of two straight tubes connected by a cone. The first straight tube has an inner diameter of 8.3 cm and length of 86 cm, the conical tube has a start inner diameter of 8.3 cm, a length of 210 cm, and a final inner diameter of 21.3 cm. The last tube has an inner diameter of 21.3 cm and a length of 50 cm. It is worthwhile to notice that an elastic membrane is placed at the ambient heat exchanger to suppress




Fig. 2. Schematic illustration of the thermoacoustic Stirling-engine. An acoustic load is placed on the resonator to control the power output of the engine. The pressure sensors are indicated by "P's".




Fig. 3. A schematic- (left) and a CAD-drawing of the torus part of the engine.

Gedeon streaming [6] which is a second-order time-averaged mass flux which circulates around the torus removing heat from the hot heat exchanger and depositing it at AHX2 without taking part to the thermoacoustic conversion process in the regenerator. This causes a heat leak that seriously degrades the performance of the engine.

3. Characterization of the engine

The characterization of the performance of the engine requires the measurement of thermal and acoustic powers. The system is instrumented so that these different quantities can be measured. The thermal power input to the engine delivered by hot air flow or the thermal power extracted by flow water from the AHX1 or AHX2 is given by

$$\dot{Q} = \rho c_p U (T_o - T_i) \quad (1)$$

Here is ρ the density of hot air or water, c_p is the specific heat of air or water, U is the volume flow rate of air or water, and T_i and T_o are the input and output temperatures of the stream flowing through the heat exchanger. The volume flow rates of air and water are measured with flow meters and the temperatures are measured by K-type thermocouples placed at the inlet and outlet of the heat exchangers.

The acoustic power produced by the engine is measured by the so-called two-microphone method [3,7]. By reference to Fig. 2, the

acoustic power flowing past the midpoint of the two pressure sensors p_3 and p_4 is given by [3,7]

$$\dot{W}_{2mic} = \frac{A}{2\omega\Delta x\rho_g} \left[\left(1 - \frac{\delta_v}{r}\right) p_3 p_4 \sin \alpha + \frac{\delta_v}{2r} (p_3^2 - p_4^2) \right] \quad (2)$$

Here p_3 and p_4 are the amplitudes of the dynamic pressures measured by the two pressure sensors, Δx is the distance between the two transducers along the resonator, α is the phase angle by which p_3 leads p_4 , ω is the angular frequency, ρ_g is the average density of the gas, and δ_v is the viscous penetration depth. The acoustic power dissipated in the load is given by Fusco et al. [7].

$$\dot{W}_{load} = \frac{\omega V_c}{2\gamma p_m} p_5 p_6 \sin \beta \quad (3)$$

where p_5 and p_6 are the amplitudes of the dynamic pressures measured at the entrance of the load and in the compliance of the load respectively, β is the phase difference between p_5 and p_6 , ω is the angular frequency, V_c is the volume of the tank of the load, p_m is the average pressure of the gas, and γ is the ratio of the isobaric to isochoric specific heats. The power, measured by the two-microphone method is the sum of the acoustic power, dissipated in the resonator section to the left of the midpoint of the two-microphones and the acoustic power, dissipated in the load




Fig. 4. (left) Picture of the AHX1; (middle) the block consisting of the regenerator holder, HHX, and TBT; (right) picture of AHX2.




Fig. 5. Measured acoustic power and performance relative to Carnot as a function of the hot air temperature for two drive ratios 4 and 6%.

$$\dot{W}_{2\text{mic}} = \dot{W}_{\text{res}} + \dot{W}_{\text{load}} \quad (4)$$

It is worthwhile to note that the two-microphone method is quite difficult due to its sensitivity to the microphone position, the phase difference, and flow conditions. The performance of the engine η is given by

$$\eta = \frac{\dot{W}}{\dot{Q}_h} \quad (5)$$

where $\dot{W}$ is the acoustic power produced by the engine (entering the resonator) which is deduced from $\dot{W}_{2\text{mic}}$ by extrapolation using the DeltaEC model of the system. The Carnot efficiency of the engine is given by

$$\eta_c = \frac{T_h - T_a}{T_h} \quad (6)$$

Here T_h is the temperature of the hot air and T_a is the average temperature of the cooling water flowing through the ambient heat exchanger. The performance relative to Carnot is defined as the ratio

$$\eta_r = \frac{\eta}{\eta_c} \quad (7)$$

4. Experimental results

The accuracy of the acoustic power measurements is first checked by plotting Expression 4 for several drive ratio's. The drive ratio is the ratio of the acoustic pressure and the average pressure. Linear fits to experimental results show a slope of about 1 which gives confidence in the two-microphone method measurements [3].

Fig. 5 shows the measured performance of the thermoacoustic engine as a function of the temperature of the hot air for two drive ratio's. The acoustic power output and the performance relative to Carnot increase as a function of the hot air temperature. At a given hot air temperature the acoustic power produced by the engine at a

drive ratio of 6% is higher than at 4%. The engine produces about 300 W of acoustic power with a performance of 41% of the Carnot performance at a drive ratio of 6% and a hot air temperature of 620 $^{\circ}\text{C}$. This relatively good performance is obtained in spite of a considerable heat leakage due to streaming in the TBT and the not optimal operation of HHX. Although a membrane is used and flow straighteners are placed in the TBT, an appreciable quantity of heat is still leaking down the TBT, which is measured at the AHX2. The flow of the hot air through the HHX decreases with the temperature which indicates an increase of the pressure drop across the HHX. This limits the heat input to the engine. An improvement of the performance might be expected by suppressing the heat leak in the TBT and improving the heat transfer in the HHX.

5. Conclusion

A hot air driven thermoacoustic-Stirling engine is designed, built, and tested. The engine produces about 300 W of acoustic power with a performance of 41% of the Carnot performance at a hot air temperature of 620 $^{\circ}\text{C}$. The performance of the engine can be improved by suppressing the heat leak down the thermal buffer tube and improving the HHX. A better solution might be to use a hot head instead of the HHX. The hot head with fins can be directly heated by the hot gases as usually done in conventional Stirling-engines.

Acknowledgements

This work has been partly funded by the European Commission within the EU-FP7 energy program: Grant Agreement no. 226415, Thematic Priority: FP7-ENERGY-2008-FET, "Thermoacoustic Technology for Energy Applications", Acronym: THATEA.

References

- [1] S. Spoelstra, M.E.H. Tijani, Thermoacoustic heat pumps for energy savings, Presented at the Seminar "Boundary Crossing Acoustics" of the Acoustical Society of the Netherlands, 2005. <http://www.ecn.nl/docs/library/report/2005/rx05159.pdf>. See also <http://www.thatea.eu/>.

- [2] P.H. Ceperley, A pistonless Stirling engine – the traveling wave heat engine, *J. Acoust. Soc. Am.* 66 (1979) 1508–1513.
- [3] S. Backhaus, G.W. Swift, A thermoacoustic Stirling heat engine: detailed study, *J. Acoust. Soc. Am.* 107 (2000) 3148–3166.
- [4] M.E.H. Tijani, S. Spoelstra, A high performance thermoacoustic engine, *J. Appl. Phys.* (2011) 110–116.
- [5] W.C. Ward, G.W. Swift, J.P. Clark, Interactive analysis, design, and teaching for thermoacoustics using DeltaEC, *J. Acoust. Soc. Am.* 123 (2008) 3546.
- [6] D. Gedeon, DC gas flows in Stirling and pulse tube cryocoolers, in: R.G. Ross (Ed.), *Cryocoolers 9*, Plenum, New York, 1997, p. 385.
- [7] A.M. Fusco, W.C. Ward, G.W. Swift, Two-sensor power measurement in lossy ducts, *J. Acoust. Soc. Am.* 91 (1992) 2229–2235.